KADUR DIVISION.

ADVERTISEMENT.

The 10th August 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 30th August 1887, for restoring the Shivane Tank, R. No. 224, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement either in the form given below showing the rates at which the different items specified will be executed, or at per cent less than the sanctioned estimate rates.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring the Shivane Tank, Tarikere Taluk"; in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.	Unit of Work.	Quantity.	Rate per unit.
Bund.			
Earthwork including watering and tamping ..	C. Yd.	13,882	
Dismantling and re-building old stone work with new jelly	"	2,168	
New stone work with new jelly complete.. ..	"	1,784	
Grade stone at every 1½ chains or 100 feet apart ..	No.	45	
Bench Mark stones 1 at every end	"	2	
Turfing (only front slope)	S. Yd.	2,720	
Kodi, 250 feet long.			
Soft rock excavation	C. Yd.	92	
Ordinary hard soil excavation	"	530	
Old stone work dismantling and re-building apron sujicut	"	296	
New stone work with new jelly complete.. ..	"	190	
Burnt brick in surki mortar	C. Ft.	6,362	
Plastering in surki chunam	Sqr.	31·50	
Burnt stone slabs, edges dressed	S. Ft.	597	
Sluices.			
Sluices masonry, ordinary design, vent 6″ × 9″ including cutting and filling the bund, first sluice at C. S. 18	R. Ft.	47	
Do do do 2nd sluice at C. S. 37 ..	"	50	

D. SITARAM RAO,
Offg. Executive Engineer.